



# PE Valve

PE Valve

## 1309-3 Valve


3 way ammonia valve, 20.5 to 35.9 tons, 3/4" male flare connections  
1300 Series 3 way Valves 3 to 175 tons 1/2" thru 3-1/8" Line Sizes

Â

**This series valve is available as a pressure differential pilot actuated valve as well as an Actuator driven valve**

Â

In the NORMAL POSITION the C and NC ports are open through the valve and the NO port is closed off inside the valve. Discharge pressure must be supplied to the 1/4" flare on the side of the valve. The 1/4" flare fitting at the pilot (below the coil) must be piped to the suction side of the compressor. In the ENERGIZED POSITION the C and NC ports are open through the valve and the NO port is closed off inside the valve. This diagram is a typical hot gas defrost configuration.





[Vendor Information](#)